

ICF Program Status



**Presented to:
Fusion Power Associates
Annual Meeting**

**By:
Dr. Christopher J. Keane
Assistant Deputy Administrator for
Inertial Confinement Fusion and the NIF Project
National Nuclear Security Administration**

September 28, 2006




Key points



- **A new vision (Complex 2030) for the nuclear weapon complex and stockpile is being implemented**
 - **High energy density physics- essential piece of Defense Programs long term science and technology base**
 - **Logic: increase margin/uncertainty**
- **The next 10 years will offer extraordinary new opportunities for inertial fusion and high energy density physics**
 - **OMEGA EP; Z/ZR; NIF and ignition; petawatt capabilities;...**
 - **Ignition and applications planned for NIF; integrated program of “non-ignition” experiments to be conducted at OMEGA/ZR/NIF**
- **Federal government vision for high energy density physics under development- response to NAS reports and Senate mark (HEDP Office)**
 - **External use program at “intermediate scale” facilities**



The nuclear weapon stockpile and complex will be transformed



Increased confidence in warhead designs and demonstration of a responsive infrastructure will enable a reduction in total stockpile size



“Getting the Job Done”

Building Confidence in the Transformation Process




NNSA short term commitments:

- Continue to deliver products to DoD.
- Eliminate backlog of surveillance units in FY 2007.
- Accelerate dismantlement of retired weapons by 49% from FY 2006 to FY 2007.
- Deliver B61-ALT357 First Production Unit (FPU) in FY 2006.
- Deliver W76 FPU in FY 2007.
- Certify the W88 with a new pit and manufacture 10 pits in FY 2007.
- Extract Tritium in FY2007.
- Support the science base by completing: pit lifetime estimates (2006), ASC Purple machine (2006), MESA (2008), DARHT (2008), and NIF (2010).
- Support an RRW decision by the Nuclear Weapons Council in Nov 2006.
- Implement starting actions to achieve Complex 2030 infrastructure vision.



The plan for use of NIF calls for first ignition experiments in FY2010



* Weapons physics experiments in support of Stockpile Stewardship


Both Bundles Meet All Performance Requirements

- Over 2 MJ equivalent in the ultraviolet
- 2 Bundles produce 300kJ @ 1 ω



LRU Installation Count >2600


- Over 43% complete and ahead of schedule
- Learning curves at 80% or better



NIF is now nearly 88% complete and on schedule



NIF Line-Replaceable-Unit installation progress through Sept. 26, 2006





NIF and ignition is a major Departmental commitment



The Secretary of Energy
Washington, DC 20585

November 18, 2005

The Honorable Pete V. Domenici
United States Senate
Washington, D.C. 20510-6050

Dear Senator Domenici:

I want to follow up our recent phone conversation regarding the Department of Energy's (DOE) national security programs and the role that the National Ignition Facility (NIF) and the Dual-Axis Radiographic Hydrotest (DARHT) play in these programs. The DOE Stockpile Stewardship Program, including our scientific tools, is vital to the continued certification and assessment of the nuclear weapons stockpile without the need for underground nuclear testing. There are two projects in particular that I would like to highlight.

Proceeding with the National Ignition Facility is essential to the success of the Stockpile Stewardship Program. NIF is the only facility capable of creating the extreme conditions of temperature and pressure required for fusion ignition and other experiments that support stockpile stewardship. I visited the NIF site at Lawrence Livermore National Laboratory, and I have concluded that NIF ignition and the experimental campaigns planned for NIF will yield vital data necessary to maintain our nuclear deterrent. NIF remains a top priority for the Department.

The DARHT Facility at Los Alamos National Laboratory is another project that has my attention and support. I know DARHT is already producing results important to stockpile stewardship and that its capabilities will increase significantly when the two-axis hydrodynamic capability is established in Fiscal Year 2008. While there have been cost and schedule concerns at DARHT in the past, the Department is resolved to complete the project on the revised baseline.

Thank you for your continued support for these vital national security programs. I look forward to working with you to complete these important facilities. If you have any questions on these important DOE initiatives, please contact me or Ms. Jill Sigal, Assistant Secretary for Congressional and Intergovernmental Affairs, at (202) 586-5450.

Sincerely,


Samuel W. Bodman



Printed on recycled paper



The OMEGA EP laser beams will be located next to the existing OMEGA facility



| Short-pulse performance | Short-pulse Beam 1 | Short-pulse Beam 2 |
|--------------------------------|---------------------------|---------------------------|
| Short pulse (IR) | 1 to 100 ps | 35 to 100 ps |
| IR energy on-target (kJ) | 2.6 | 2.6 |
| Intensity (W/cm ²) | 6×10^{20} | $\sim 4 \times 10^{18}$ |
| Focusing | > 80% in 20 μm | > 80% in 40 μm |




OMEGA EP laser bay- August 2006





ZR and Z Beamlet- petawatt are important additions to program capability



- The ZR project is upgrading the performance of Z
 - 18 MA to 26 MA
 - 2x increase in diagnostic access
 - 2x shot rate capability





- The Z-Petawatt project is upgrading the capability of Z-Beamlet
 - 2 TW to 1 PW
 - backlighter $h\nu$ 9 - 25 keV
 - integrated FI experiments on ZR

• The ZR and Z-Petawatt facilities will begin operations in 2007.

The last Z shot was July 26, 2006; refurbishment is in progress.



Z

Refurbished Z





Remove existing hardware
(7/27/06 – 8/23/06)

Install new hardware
(start expected late October)




Remove existing
oil/water wall
(8/24/06 – 9/18/06)

Construct new oil/water wall
and reinforce floor structures
(9/19/06 – present)






High Average Power Laser Program is a Congressionally funded program within NNSA



**Review report from OFES/NNSA review of
NRL FTF program to be available shortly**



The *long-term* goal of Z-Pinch IFE is to produce an economically attractive power plant using high-yield z-pinch-driven targets (~ 3 GJ) at low rep-rate per chamber (~ 0.1 Hz)




Z-Pinch IFE DEMO (ZP-3, the first study) used 12 chambers, each with 3 GJ at 0.1 Hz, to produce 1000 MWe

The *near-term* goal of Z-Pinch IFE is to address the science issues of repetitive pulsed power drivers, recyclable transmission lines, high-yield targets, and thick-liquid wall chamber power plants



Academic Alliances







ICF Program FY2007 Budget Status



| MTE | FY06 Approp | FY07 Presid | FY07 House | FY07 Senate |
|-------------------------------|----------------|----------------|----------------|----------------|
| 10.1 Ignition | 74,859 | 79,763 | 79,763 | 69,763 |
| 10.2 Stock Sup | 19,673 | 5,872 | 5,872 | 25,872 |
| 10.3 Diagnostics | 42,578 | 45,959 | 55,959 | 42,578 |
| 10.4 Pulse Power | 10,902 | 10,603 | 10,603 | 10,603 |
| 10.5 Universities | 7,623 | 8,903 | 8,903 | 0 |
| 10.7 Targets & Ops | 63,977 | 43,021 | 58,021 | 53,021 |
| 10.8 Inertial Fusion | 47,520 | 0 | 40,000 | 0 |
| 10.10 Petawatt | 34,650 | 2,213 | 14,213 | 0 |
| | | | | |
| 10.9 Demo | 101,307 | 143,438 | 143,438 | 129,000 |
| NIF Construction | 140,494 | 111,419 | 111,419 | 81,419 |
| Total | 543,583 | 451,191 | 528,191 | 412,256 |



Federal vision for basic HEDP is under development



OSTP chartered interagency task force (C. Keane, D. Kovar, chairs) will produce report by end of CY2006



Key points




- **A new vision (Complex 2030) for the nuclear weapon complex and stockpile is being implemented**
 - **High energy density physics- essential piece of Defense Programs long term science and technology base**
 - **Logic: increase margin/uncertainty**
- **The next 10 years will offer extraordinary new opportunities for inertial fusion and high energy density physics**
 - **OMEGA EP; Z/ZR; NIF and ignition; petawatt capabilities;...**
 - **Ignition and applications planned for NIF; integrated program of “non-ignition” experiments to be conducted at OMEGA/ZR/NIF**
- **Federal government vision for high energy density physics under development- response to NAS reports and Senate mark (HEDP Office)**
 - **External use program at “intermediate scale” facilities**




Backups



The objectives of the ZR Project are to extend Z's life in a balanced way and to exercise SNL's pulsed power research and engineering capabilities for future endeavors.



The major ICF facilities provide unique capabilities



Cost, availability, diagnostics, reproducibility, precision, and flexibility ultimately determine which facilities are used for specific experiments.



The revised NIF Project baseline completes in Q2FY2009 and supports Ignition 2010



| | FY01 | FY02 | FY03 | FY04 | FY05 | FY06 | FY07 | FY08 | FY09 | FY10 |
|----------------|---------------------------------|-------------------------------|------|--|--------------------------------|--|--------------------------------|--------------------------------------|--|------|
| Level 0 | | | | | | | | | △ CD4 Approval to Begin Operations | |
| Level 1 | ▲ End Conventional Construction | | | | | ▲ BIS Complete | △ Complete LB1 Laser Light MPR | △ Submit Final Safety Basis Document | △ Submit Readiness Assessment Documentation | |
| Level 2 | | ▲ Target Chamber Positioned | | | ▲ Laser Glass Melting Complete | | | | | |
| | | ▲ Control Room Turnover | | | | △ Deliver LB Automated Bundle Shot Controls | | | | |
| | | ▲ LB2 Ready for Transporter | | | | △ Deliver 80 kJ to Switchyard Calorimeters (single bundle) | | | | |
| | | ▲ PCS Installation Begins | | | | △ Deliver LB Multi-Bundle Controls | | | | |
| | | ▲ LB2, CL3 Beampath Installed | | | | △ Complete Single Bundle Performance Qualification in PDS | | | | |
| | | ▲ 1st LB2 Flashlamp Installed | | | | △ Deliver One Cluster Integrated Controls | | | | |
| | | ▲ OAB Operational | | | | △ First Cluster - Energy to Switchyard Calorimeters | | | | |
| | | ▲ TARPOS Installed | | | | △ Second Cluster - Energy to Switchyard Calorimeters | | | | |
| | | | | ▲ 1st Light TCC | | | | | △ Complete LB LRU Installations | |
| | | | | ▲ 1st 1ω Light (10kJ) | | | | | △ Complete Performance Qualification of a Single Bundle at TCC | |
| | | | | ▲ SY2 Beampath Ready for Commissioning | | | | | △ Complete Operational Qualification of 96 Beams (Two Clusters at TCC) | |
| | | | | | | | | | △ Complete Installation Qualification of all LRUs (192 beams) | |


△ DOE Milestone Commitment Date
▲ Completed Milestones




High resolution x-ray backlighting is an important new diagnostic now in routine use on Z



X-ray backlighting using a bent crystal imaging detector system




3.2 mm dia. capsule radiograph ($C_r = 1.7$)




Z-pinch implosion

z1397: Intensity (phot/micron²)




Complex hydrodynamics





ICF FY 2005 Budget by Element



Total Budget = \$536.7 M

- NIC
- Weapons Physics
- Pulsed Power
- University Grants
- Inertial Fusion Technology
- Petawatt Laser Development
- NIF Project

RTBF Z Operations – 11.8M

RTBF Z-backlighter laser – 13M



Administrator & Under Secretary for Nuclear Security, Linton F. Brooks

Principal Deputy Administrator
(Vacant)

Associate Principal Deputy Administrator
James Cavanagh


Chief of Staff
William Barker, Jr.

Administrator's Staff

Director, Defense Nuclear Counterintelligence
General Counsel
Director, Policy Planning, Assessment, & Analysis
Environment, Safety, & Health Advisor
Director, Congressional, Intergovernmental and Public Affairs
Chief, Defense Nuclear Safety

Office of the Deputy Under Secretary for Counterterrorism

Steven Aoki
NA-4





NIF Funding Profile

